


## LOAD MOMENT INDICATOR SYSTEM

# MARK 4E/2



CALIBRATION MANUAL


P/N 031-300-190-074, Rev. E, 12/17/2008

#### NOTICE

The information in this document is subject to change without notice. Hirschmann makes no warranty of any kind with regard to this material, including, but not limited to the implied warranties of merchantability and fitness for a particular purpose.


Hirschmann shall not be liable for errors contained in this manual or for incidental or consequential damages in connection with the furnishing, performance, or use of this manual. This document contains proprietary information, which is protected by copyright. All rights are reserved.

No part of this document may be photocopied, reproduced, or translated to another language without the prior written consent of Hirschmann.



### TABLE OF CONTENTS

1	GENERAL INFORMATION 1
2	MATERIAL LIST 1
3	WARNINGS 1
4	CALIBRATION PROCEDURE
	4.1 I. C. INSTALLATION
	4.2 PANEL START UP
	4.3 ANGLE AND LENGTH PRE-CALIBRATION
	4.4 ENTERING CALIBRATION MENU
	4.5 ANGLE CALIBRATION
	4.6 LENGTH CALIBRATION 6
	4.7 RATIO CALIUBRATION
	4.8 RADIUS OFFSET CALIBRATION
	4.9 LOAD CALIBRATION
	4.10 DEFLECTION CALIBRATION 21
	4.11 LOAD MOMENT SHUT OFF
	4.12 MEASURE
5	MENU FLOW CHART
6	CALIBRATION SUMMARY TABLE



### 1 GENERAL INFORMATION

The Load Moment Indicator System Mark 4E/2 must be calibrated after completing system installation, crane modification, or anytime there is an indication of inaccuracy. The calibration will match the sensors installed on the crane.

Prior to starting the calibration, it is advised to first read over this procedure in its entirety. The purpose of this manual is to provide calibration information required before operating the system. Refer to the <u>Operator's Manual</u> for system description and console controls.

REFERENCE INFORMATION: Load Moment Indicator System Mark 4E/2 Operator's Manual. 031-300-190-073

#### 2 MATERIAL LIST

- software EPROMs and calibration information package
- EPROM puller
- Inclinometer or Digital Level
- 200' tape measure ft/meters
- digital multimeter a set of leads
- test weights; (Test loads are determined by the Crane Load Charts included with the calibration information).

<u>NOTE</u>: To comply with the SAE J376 standards the test load must be to a known accuracy of  $\pm 1\%$ .

#### **3 WARNINGS**

Always refer to operational instructions and load charts that are provided by the crane manufacturer for specific crane operation and load limits.

**TECHNICAL SER** 

The Load Moment Indicator System Mark 4E/2 is not and shall not be a substitute for good operator judgment, experience, or use of acceptable safe operating procedures.

The operator is responsible for operating the crane within the manufacturer's specified parameters.

The crane operator shall ensure that all warnings and instructions provided by the manufacturer are fully understood, observed, and remain with the crane.

Prior to operating the crane, the operator must carefully read and understand the information in the <u>Operator's Manual</u> so that he knows the operation and limitations of the Load Moment Indicator System Mark 4E/2.

## / WARNING


BEFORE OPERATION OF THE CRANE, THE SYSTEM MUST BE CALIBRATED. ALL STEPS MUST BE FOLLOWED AND COMPLETED. TO PREVENT MATERIAL DAMAGE AND SERIOUS, OR EVEN FATAL, ACCIDENTS, THE CORRECT ADJUSTMENT OF THE SYSTEM HAS TO BE ENSURED BEFORE STARTING THE CRANE OPERATION.

### 4 CALIBRATION PROCEDURE

#### 4.1 I.C. Installation

- 4.1.1 Check and verify that the Load Chart in the enclosed booklet matches the Load Chart in the crane. If the Load Charts do not match, please contact PAT America Inc.
- 4.1.2 Install the EPROMs that are received with the booklet by plugging them into the proper socket and in the proper direction, as shown below.

WARNING: If the EPROMs are put into the sockets improperly they will be destroyed and new EPROMs will have to be purchased.



#### 4.2 Panel start up

4.2.1 Turn on power to the system. The panel will display E: 1140, E:1141 or E:1142 (if these  $\nabla$ error messages do not appear continue to Section 4.3). Push Δ , then the display will change to: ACCESS CODE 0000000 P ÞÞ 4.2.2 To enter the ACCESS CODE push button to cursor to each digit and the  $\bigtriangleup$  $\odot$ buttons to change number to get the proper menu digit. The ACCESS CODE or is 001001. P) ¢¢ 4.2.3 Push button and panel will display: CKSUM EP CKSUM EEP CKSUM PRG RESET P>  $\not\approx$ 4.2.4 To checksum new EPROMs: button at EAGH of these menu titles, doing a RESET  $\nabla$  $\overline{\mathbf{v}}$ Δ last. To select a menu title, use the or buttons until menu title blinks then ÞÞ button. After check summing EPROMs. **RESET** the system and panel will push enter the Program Menu. buttons to select the configuration the crane is configured. Push 4.2.5 Use the P)  $\not\approx$ button to get to Operating Screen.

#### 4.3 Angle and length pre-calibration setup (Voltage/Current)

- 4.3.1 With boom fully retracted and at lowest possible angle, set minimum angle and length voltages to approximately 1V for voltage sensors or 4mA for current sensors. Angle signal can be measured between terminal #44 (GND) and #56 (signal) in the CPU. Length signal can be measured between terminals #44 (GND) and #53 (signal) of the CPU.
- 4.3.2 (Voltage) Angle voltages are checked in the cable reel with ground lead of voltmeter put on terminal # 1 and the positive lead on terminal # 5 on the terminal strip. Loosen setscrews on angle bracket. Turn angle bracket (allowing pendulum to swing freely as the

boom goes up) until the pendulum and rubber bumper are barely touching. Retighten setscrews. Adjust voltage by loosening the three screws by the angle potentiometer and turning potentiometer until approximately 1.000 VDC is reached.

- 4.3.3 (Voltage) Length voltages are checked with ground lead of voltmeter put on terminals # 1 and the positive lead on terminal # 2 on the terminal strip. Adjust voltage by turning wiper arm (located behind white nylon gear and on the shaft of the length potentiometer) to approximately 1.000 VDC.
- 4.3.4 <u>(Current) Angle</u> The angle sensor must be level. Adjust the level of the angle sensor by loosening the socket head cap screws and aligning the top of the angle sensor until parallel with the boom.

The input signal operating window is 4 to 20mA, measured in series at the analog input terminal OR 1V to 5V, measured in parallel between the analog input and ground (GND) terminals. At 4mA the voltage is 1V and at 20mA the voltage is 5V.

4.3.5 <u>(Current) Length</u> - Reset length potentiometer in length angle transducer (screw is located in center of white gear); with boom fully retracted, turn potentiometer carefully counter-clockwise until it stops. Recheck length and angle display.

The input signal operating window is 4 to 20mA, measured in series at the analog input terminal OR 1V to 5V, measured in parallel between the analog input and ground (GND) terminals. At 4mA the voltage is 1V and at 20mA the voltage is 5V.

#### 4.4 Entering Calibration Menu

4.4.1 From the <u>Operating Screen</u> (shown below **Diagram #1**) enter the Calibration menu by

pushing and holding the  $\stackrel{\leftrightarrow}{\longrightarrow}$  button then push the  $\stackrel{\leftrightarrow}{\longrightarrow}$  button.




Diagram #

1

#### 4.5 Angle Calibration:

- 4.5.1 <u>With Boom at Zero Degrees.</u>
- 4.5.2 Go to the **Calibration Menu**. (Refer to Section 4.4)

 $\bigtriangleup$ 

- 4.5.3 Push the or button until NORM menu title blinks, then push the button.
- 4.5.4 Push the or button until **ANGLE** menu title blinks, then push the button.
- 4.5.5 Verify boom is at 0 degrees with an inclinometer or digital level.
- 4.5.6 Push the or button until **MAXIMUM (signal)** menu title blinks, then push the button. (*note: 20mA at 0°*)
- 4.5.7 Push the button until all digits have been verified with the proper value of **000.0** at 0 degrees.
- 4.5.8 Hoist the boom all the way up and check angle, using an inclinometer or digital level.

4.5.9 Push the or button until MINIMUM (signal) menu title blinks, then push the TECHNICAL SERVICES

☆ button. *(note: 4mA at 90°*)

P

 $\bigtriangleup$ 

 $\land$ 

P)

4.5.10 Push the button to change the first digit of the angle displayed to match the digital level reading. Select the next digit by pushing the or button until the proper

number for that digit is reached. Continue this process until all digits have been corrected. For Example, if the angle given by digital level was 76.5 degrees, then the

display should read 076.5 before the button is pushed for the last time.


- 4.5.11 Push the dot or button until **ADJUST** menu title blinks, then push the button.
- 4.5.12 Push the dorest or button (since **EXIT** menu title is at the end of each menu push button) until **EXIT** menu title blinks, then push the button until you return to the Operating Screen. (diagram # 1)
- 4.5.13 Boom down to 60 degrees, using crane angle indicator or digital level to verify proper angle indication.

P>

#### 4.6 Length Calibration: 4.6.1 With Fully Retracted Boom 4.6.2 Go to the Calibration Menu. (Refer to Section 4.4) P $\bigtriangleup$ $\Rightarrow$ ЪФ 4.6.3 Push the button until NORM menu title blinks, then push the or button. P ЪФ $\odot$ button until LENGTH menu title blinks, then push the 4.6.4 Push the button. Verify boom is at fully retracted. 4.6.5 P ЪФ $\Rightarrow$ 4.6.6 button until MINIMUM menu title blinks, then push the Push the button. P> Þ button until all digits have been verified with the proper value, which will 4.6.7 Push the be minimum boom length of the load chart. 4.6.8 Fully extend the boom. P $\bigtriangleup$ ÷ 4.6.9 Push the button until MAXIMUM menu title blinks, then push the or button. P ¢¢ 4.6.10 Push the button until all digits have been verified with the proper value, which will be maximum boom length of the load chart P $\overline{\mathbb{T}}$ Ř 4.6.11 Push the button until ADJUST menu title blinks, then push the or button. P $\triangle$ Þ\$ $\odot$ button until **EXIT** menu title blinks, then push the 4.6.12 Push the or button until you return to the Operating Screen. (diagram #1) 4.6.13 Fully retract the boom. Check the cable reel when retracting to verify that the reel is spooling properly. If the reel is not spooling properly, adjust the first roller guide until

spooling is correct.

#### 4.7 Ratio Calibration:




#### 4.9 Load Calibration:

- 4.9.1 Remove all extension, jibs, etc. from the side of the boom when calibrating Main Boom only configurations.
- 4.9.2 Select program for the cranes configuration. (example: On Outriggers Main Boom )
- 4.9.3 Verify **OWN WEIGHT** pressure profile for minimum boom length is correct.

#### 4.9.4 Boom to 15 degrees.

- 4.9.5 Get **OWN WEIGHT** value by adding block weights + deducts. If load indication is correct go to step 4.9.14.
- 4.9.6 Go to the **Calibration Menu**. (Refer to Section 4.4)
- P $\widehat{\mathbf{v}}$ Ř 4.9.7 Push the button until SETUP menu title blinks, then push the or button.  $\bigtriangledown$  $\bigtriangleup$  $\widehat{\mathbb{T}}$ 4.9.8 Push the button until **CORRECTION** menu title blinks, then push the or P  $\not\approx$ button.  $\nabla$ P ф¢ 4.9.9 Select current boom LENGTH by pushing the and push the or button. 4.9.10 Push the button until OWN-WEIGHT menu title blinks, then push the ٥r P ₿ \$ button.  $\triangle$  $\not\approx$  $\odot$ button until P4 menu title blinks, then push the 4.9.11 Push the button. or  $\nabla$  $\overline{\mathbb{T}}$ button to change % until ACT. LOAD = OWN WEIGHT 4.9.12 Push the or P) ¢¢ (Block Weights + Deducts), then push the button.  $\bigtriangleup$ P  $\Rightarrow$ Þ\$ button until EXIT menu title blinks, then push the 4.9.13 Push the or button. Until you return to the Operating Screen. (diagram #1)
- 4.9.14 Boom to 30 degrees.
- 4.9.15 Get **OWN WEIGHT** value by adding block weights + deducts. If load indication is correct go to step 4.8.23.
- 4.9.16 Go to the **Calibration Menu**. (Refer to Section 4.4)

4.9.17	Push the $\checkmark$ or $\checkmark$ button until <b>SETUP</b> menu title blinks, then push the button.
4.9.18	Push the $\checkmark$ or $\checkmark$ button until <b>CORRECTION</b> menu title blinks, then push the $\checkmark$ button.
4.9.19	Select current boom <b>LENGTH</b> by pushing the $\checkmark$ or $\checkmark$ and push the $\checkmark$ button.
4.9.20	Push the $\checkmark$ or $\checkmark$ button until <b>OWN-WEIGHT</b> menu title blinks, then push the $\checkmark$
	button.
4.9.21	Push the $\checkmark$ or $\checkmark$ button until <b>P3</b> menu title blinks, then push the $\checkmark$ button.
4.9.22	Push the or button to change % until ACT. LOAD = OWN WEIGHT
	(Block Weights + Deducts), then push the 😾 button.
4.9.23	Boom to 45 degrees.
	TECHNICAL SERVICES
4.9.24	Get <b>OWN WEIGHT</b> value by adding block weights + deducts. If load indication is correct go to step 4.8.33.
4.9.25	Go to the <b>Calibration Menu</b> . (Refer to Section 4.4)
4.9.26	Push the $\checkmark$ or $\checkmark$ button until <b>SETUP</b> menu title blinks, then push the $\checkmark$ button.
4.9.27	Push the $\checkmark$ or $\checkmark$ button until <b>CORRECTION</b> menu title blinks, then push the $\checkmark$ button.
4.9.28	Select current boom <b>LENGTH</b> by pushing the or and push the button.
4.9.29	Push the $\checkmark$ or $\checkmark$ button until <b>OWN-WEIGHT</b> menu title blinks, then push the $\checkmark$ button.



- 4.9.42 Boom to 70 degrees.
- 4.9.43 Get **OWN WEIGHT** value by adding block weights + deducts. If load indication is correct go to step 4.8.51.

button until P1 menu title blinks, then push the

- 4.9.50 Push the  $\checkmark$  or  $\checkmark$  button to change % until ACT. LOAD = OWN WEIGHT (Block Weights + Deducts), then push the  $\checkmark$  button.
- 4.9.51 Boom to various intermediate angles to verify load indication is indicating OWN WEIGHT correct. If indication is correct go to Section 4.9.52. If there are variances in the indication this may be do to the cranes hydraulics. If the OWN WEIGHT profile is not good go to Section 4.13 4.17 to have MEARSURE generate the pressure profiles.
- 4.9.52 Verify **LOAD** pressure profile for minimum boom length is correct by booming to 15 degrees.
- 4.9.53 Boom to 15 degrees.

4.9.49 Push the

- 4.9.54 Get **LOAD** value by adding known weight (a weight to allow you to get to longest radius or lowest angle of the load chart) + block weights + deducts. If load indication is correct go to step 4.8.63.
- 4.9.55 Go to the **Calibration Menu**. (Refer to Section 4.4)

 $\Rightarrow$ 

4.9.56 Push the or button until **SETUP** menu title blinks, then push the button.

ÞÞ

button.

4.9.57	Push the $\checkmark$ or $\checkmark$ button until <b>CORRECTION</b> menu title blinks, then push the
	button.
4.9.58	Select current boom <b>LENGTH</b> by pushing the $\checkmark$ or $\checkmark$ and push the $\checkmark$
4.9.59	Push the $\checkmark$ or $\checkmark$ button until LOAD menu title blinks, then push the $\checkmark$ button.
4.9.60	Push the $\checkmark$ or $\checkmark$ button until <b>P4</b> menu title blinks, then push the $\checkmark$ button.
4.9.61	Push the or button to change % until ACT. LOAD = LOAD
	(Known Weight + Block Weights + Deducts), then push the 🔛 button.
4.9.62	Push the $\bigcirc$ or $\bigcirc$ button until <b>EXIT</b> menu title blinks, then push the $\bigcirc$ button. Until you return to the <u>Operating Screen</u> . (diagram # 1)
4.9.63	Boom to 30 degrees.
4.9.64	Get <b>LOAD</b> value by adding known weight + block weights + deducts. If load indication is correct go to step 4.8.72.
4.9.65	Go to the Calibration Menu. (Refer to Section 4.4)
4.9.66	Push the or button until <b>SETUP</b> menu title blinks, then push the button.
4.9.67	Push the or button until <b>CORRECTION</b> menu title blinks, then push the button.
4.9.68	Select current boom <b>LENGTH</b> by pushing the $\checkmark$ or $\checkmark$ and push the $\checkmark$
4.9.69	Push the $\checkmark$ or $\checkmark$ button until LOAD menu title blinks, then push the $\checkmark$ button.
4.9.70	Push the $\checkmark$ or $\checkmark$ button until <b>P3</b> menu title blinks, then push the $\checkmark$ button.

4.9.71	Push the or button to change % until ACT. LOAD = LOAD
	(Known Weight + Block Weights + Deducts), then push the button.
4.9.72	Boom to 45 degrees.
4.9.73	Get <b>LOAD</b> value by adding known weight + block weights + deducts. If load indication is correct go to step 4.8.82.
4.9.74	Go to the Calibration Menu. (Refer to Section 4.4)
4.9.75	Push the $\checkmark$ or $\checkmark$ button until <b>SETUP</b> menu title blinks, then push the button.
4.9.76	Push the or button until CORRECTION menu title blinks, then push the button.
4.9.77	Select current boom LENGTH by pushing the $\checkmark$ or $\checkmark$ and push the $\checkmark$
4.9.78	Push the or button until LOAD menu title blinks, then push the button.
4.9.79	Push the $\checkmark$ or $$ button until <b>P2</b> menu title blinks, then push the $\checkmark$ button.
4.9.80	Push the or button to change % until ACT. LOAD = LOAD
	(Known Weight + Block Weights + Deducts), then push the 🔛 button.
4.9.81	Push the $\checkmark$ or $\checkmark$ button until <b>EXIT</b> menu title blinks, then push the $\checkmark$ button. Until you return to the <u>Operating Screen</u> . (diagram # 1)

#### 4.9.82 Boom to 60 degrees.

- 4.9.83 Get **LOAD** value by adding known weight + block weights + deducts. If load indication is correct go to step 4.8.91.
- 4.9.84 Go to the **Calibration Menu**. (Refer to Section 4.4)

4.9.85	Push the $\checkmark$ or $\checkmark$ button until <b>SETUP</b> menu title blinks, then push the $\checkmark$ button.
4.9.86	Push the $\checkmark$ or $\checkmark$ button until <b>CORRECTION</b> menu title blinks, then push the $\checkmark$ button.
4.9.87	Select current boom <b>LENGTH</b> by pushing the $\checkmark$ or $\checkmark$ and push the $\checkmark$
4.9.88	Push the $\checkmark$ or $\checkmark$ button until LOAD menu title blinks, then push the $\checkmark$ button.
4.9.89	Push the $\checkmark$ or $\checkmark$ button until <b>P1</b> menu title blinks, then push the $\checkmark$ button.
4.9.90	Push the $\checkmark$ or $\checkmark$ button to change % until <b>ACT. LOAD = LOAD</b>
	(Known Weight + Block Weights + Deducts), then push the 🖾 button.
4.9.91	Boom to 70 degrees.
4.9.92	Get <b>LOAD</b> value by adding block weights + deducts. If load indication is correct go to step 4.9.100.
4.9.93	Go to the Calibration Menu. (Refer to Section 4.4)
4.9.94	Push the $\checkmark$ or $\checkmark$ button until <b>SETUP</b> menu title blinks, then push the button.
4.9.95	Push the or button until <b>CORRECTION</b> menu title blinks, then push the button.
4.9.96	Select current boom <b>LENGTH</b> by pushing the $\checkmark$ or $\checkmark$ and push the $\checkmark$
4.9.97	Push the $\checkmark$ or $\checkmark$ button until LOAD menu title blinks, then push the $\checkmark$ button.
4.9.98	Push the $\checkmark$ or $\checkmark$ button until <b>P1</b> menu title blinks, then push the $\checkmark$ button.

4.9.99	Push the or button to change% until <b>ACT. LOAD = LOAD</b>
	(Known Weight + Block Weights + Deducts), then push the

- 4.9.100 After Load Indication has been calibrated for this length it is recommended that a load moment shutoff be tested. Refer to Section 4.11 Page 22
- 4.9.101 EXTEND BOOM to the next boom length to be calibrated. (In most cases the next boom length is fully extended, but with cranes with non-synchronized and longer length booms there are middle pressure profiles. To determine this go to steps 4.9.92 4.9.95 and use up or down to get all pressure profile lengths)
- 4.9.102 Verify **OWN WEIGHT** pressure profile for indicated boom length is correct.
- 4.9.103 Boom to lowest possible angle on load chart for this configuration.
- 4.9.104 Get **OWN WEIGHT** value by adding block weights + deducts. If load indication is correct go to step 4.8.113.

4.9.105 Go to the Calibration Menu. (Refer to Section 4.4)
4.9.106 Push the or button until SETUP menu title blinks, then push the $\overrightarrow{\mathbb{P}}$
4.9.107 Push the or button until <b>CORRECTION</b> menu title blinks, then push the button.
4.9.108 Select current boom <b>LENGTH</b> by pushing the button.
4.9.109 Push the or button until <b>OWN-WEIGHT</b> menu title blinks, then push the button.
4.9.110 Push the $\checkmark$ or $\checkmark$ button until <b>P4</b> menu title blinks, then push the $\checkmark$ button.
4.9.111 Push the or button to change % until ACT. LOAD = OWN WEIGHT
(Block Weights + Deducts), then push the $\bigcirc$ button.

- P  $\Rightarrow$  $\not\approx$ 4.9.112 Push the button until **EXIT** menu title blinks, then push the button. or Until you return to the Operating Screen. (diagram # 1) 4.9.113 Boom to 30 degrees. 4.9.114 Get **OWN WEIGHT** value by adding block weights + deducts. If load indication is correct go to step 4.8.122. 4.9.115 Go to the **Calibration Menu**. (Refer to Section 4.4) P> ₿ Ø button until SETUP menu title blinks, then push the 4.9.116 Push the or button.  $\overline{\mathbb{T}}$ 4.9.117 Push the button until CORRECTION menu title blinks, then push the ٥r P> ÞÞ button.  $\overline{\diamondsuit}$ Ř 4.9.118 Select current boom LENGTH by pushing the and push the or button.  $\Delta$  $\Rightarrow$ menu title blinks, then push the 4.9.119 Push the button until OWN-WEIGHT P ¢¢ button.  $\Rightarrow$ ÞÞ 4.9.120 Push the button until P3 menu title blinks, then push the button. button to change % until ACT. LOAD = OWN WEIGHT 4.9.121 Push the or P (Block Weights + Deducts), then push the button.
- 4.9.122 Boom to 45 degrees.
- 4.9.123 Get **OWN WEIGHT** value by adding block weights + deducts. If load indication is correct go to step 4.8.132.
- 4.9.124 Go to the Calibration Menu. (Refer to Section 4.4)
- 4.9.125 Push the dot or button until **SETUP** menu title blinks, then push the button.

4.9.126 Push the or button until <b>CORRECTION</b> menu title blinks, then push the
button.
4.9.127 Select current boom <b>LENGTH</b> by pushing the or and push the button.
4.9.128 Push the or button until <b>OWN-WEIGHT</b> menu title blinks, then push the button.
4.9.129 Push the $\checkmark$ or $\checkmark$ button until <b>P2</b> menu title blinks, then push the $\checkmark$ button.
4.9.130 Push the or button to change% until <b>ACT. LOAD = OWN WEIGHT</b>
(Block Weights + Deducts), then push the button.
4.9.131 Push the or button until <b>EXIT</b> menu title blinks, then push the button. Until you return to the <u>Operating Screen</u> . (diagram # 1)
4.9.132 Boom to 60 degrees. TECHNICAL SERVICES
4.9.133 Get <b>OWN WEIGHT</b> value by adding block weights + deducts. If load indication is correct go to step 4.8.141.
4.9.134 Go to the Calibration Menu. (Refer to Section 4.4)
4.9.135 Push the or button until <b>SETUP</b> menu title blinks, then push the button.
4.9.136 Push the or button until <b>CORRECTION</b> menu title blinks, then push the button.
4.9.137 Select current boom <b>LENGTH</b> by pushing the button.
4.9.138 Push the or button until <b>OWN-WEIGHT</b> menu title blinks, then push the button.

4 9 139 Push the
4.9.139 Push the $\checkmark$ or $\checkmark$ button until <b>P1</b> menu title blinks, then push the $\checkmark$ button.
4.9.140 Push the or button to change % until ACT. LOAD = OWN WEIGHT
(Block Weights + Deducts), then push the button.
4.9.141 Boom to 70 degrees.
4.9.142 Get <b>OWN WEIGHT</b> value by adding block weights + deducts. If load indication is correct go to step 4.8.21.
4.9.143 Go to the Calibration Menu. (Refer to Section 4.4)
4.9.144 Push the $\checkmark$ or $\checkmark$ button until <b>SETUP</b> menu title blinks, then push the button.
4.9.145 Push the or button until <b>CORRECTION</b> menu title blinks, then push the button.
4.9.146 Select current boom LENGTH by pushing the or and push the button.
4.9.147 Push the the button until OWN-WEIGHT menu title blinks, then push the button.
4.9.148 Push the $\overrightarrow{a}$ or $\overrightarrow{a}$ button until <b>P1</b> menu title blinks, then push the button.
4.9.149 Push the $\checkmark$ or $\checkmark$ button to change % until ACT. LOAD = OWN WEIGHT
(Block Weights + Deducts), then push the button.
4.9.150 Boom to various intermediate angles to verify load indication is indicating <b>OWN WEIGHT</b>


- 4.9.150 Boom to various intermediate angles to verify load indication is indicating OWN WEIGHT correct. If indication is correct go to Section 4.9.150. If there are variances in the indication this may be do to the cranes hydraulics. If the OWN WEIGHT profile is not good go to Section 4.13 to have MEARSURE generate the pressure profiles.
- 4.9.151 Verify **LOAD** pressure profile for maximum boom length is correct.
- 4.9.152 Get **LOAD** value by adding known weight (a weight to allow you to get to longest radius or lowest angle of the load chart) + block weights + deducts. If load indication is correct go to step 4.8.62.

<u>Boom to lowest possible angle on load chart for this configuration</u>. **WARNING:** Do not exceed Load Chart Capacity for **LOAD**, The operator is responsible for operating the crane within the manufacturer's specified parameters.

4.9.153 Go to the Calibration Menu. (Refer to Section 4.4)

4.9.154 Push the or button until <b>SETUP</b> menu title blinks, then push the button.
4.9.155 Push the or button until <b>CORRECTION</b> menu title blinks, then push the button.
4.9.156 Select current boom <b>LENGTH</b> by pushing the or and push the button.
4.9.157 Push the $\checkmark$ or $\checkmark$ button until LOAD menu title blinks, then push the button.
4.9.158 Push the or button until P4 menu title blinks, then push the button.
4.9.159 Push the down of the services of the services
(Known Weight + Block Weights + Deducts), then push the button.
4.9.160 Push the or button until <b>EXIT</b> menu title blinks, then push the button. Until you return to the <u>Operating Screen</u> . (diagram #1)

- 4.9.161 Boom to 30 degrees.
- 4.9.162 Get **LOAD** value by adding known weight + block weights + deducts. If load indication is correct go to step 4.8.170.
- 4.9.163 Go to the Calibration Menu. (Refer to Section 4.4)



4.9.166 Select current boom LENGTH by pushing the or and push the
4.9.166 Select current boom LENGTH by pushing the button.
4.9.167 Push the $rightarrow$ or $rightarrow$ button until <b>LOAD</b> menu title blinks, then push the $rightarrow$ button.
4.9.168 Push the $\checkmark$ or $\checkmark$ button until <b>P3</b> menu title blinks, then push the $\checkmark$ button.
4.9.169 Push the or button to change % until <b>ACT. LOAD = LOAD</b>
(Known Weight + Block Weights + Deducts), then push the button.
4.9.170 Boom to 45 degrees.
4.9.171 Get <b>LOAD</b> value by adding known weight + block weights + deducts. If load indication is correct go to step 4.8.180.
4.9.172 Go to the Calibration Menu. (Refer to Section 4.4)
4.9.173 Push the or button until SETUP menu title blinks, then push the button.
4.9.174 Push the time or button until CORRECTION menu title blinks, then push the TECHNICAL SERVICES
4.9.175 Select current boom <b>LENGTH</b> by pushing the button.
4.9.176 Push the $\checkmark$ or $\checkmark$ button until <b>LOAD</b> menu title blinks, then push the $\checkmark$ button.
4.9.177 Push the $\checkmark$ or $\checkmark$ button until <b>P2</b> menu title blinks, then push the button.
4.9.178 Push the or button to change % until <b>ACT. LOAD = LOAD</b>
(Known Weight + Block Weights + Deducts), then push the button.
4.9.179 Push the or button until <b>EXIT</b> menu title blinks, then push the button. Until you return to the <u>Operating Screen</u> . (diagram # 1)

<sup>4.9.180</sup> Boom to 60 degrees.

4.9.181 Get **LOAD** value by adding known weight + block weights + deducts. If load indication is correct go to step 4.8.189.

4.9.182 Go to the Calibration Menu. (Refer to Section 4.4)
4.9.183 Push the or button until SETUP menu title blinks, then push the button.
4.9.184 Push the or button until <b>CORRECTION</b> menu title blinks, then push the button.
4.9.185 Select current boom <b>LENGTH</b> by pushing the button. $\overrightarrow{\bigcirc}$ or $\overrightarrow{\bigcirc}$ and push the $\overrightarrow{\bigcirc}$
4.9.186 Push the $\checkmark$ or $\checkmark$ button until <b>LOAD</b> menu title blinks, then push the $\checkmark$ button.
4.9.187 Push the $\checkmark$ or $\checkmark$ button until <b>P1</b> menu title blinks, then push the $\checkmark$ button.
4.9.188 Push the or button to change % until ACT. LOAD = LOAD
(Known Weight + Block Weights + Deducts), then push the button.
4.9.189 Boom to 70 degrees.
4.9.190 Get <b>LOAD</b> value by adding block weights + deducts. If load indication is correct go to step 4.8.21.
4.9.191 Go to the Calibration Menu. (Refer to Section 4.4)
4.9.192 Push the or button until SETUP menu title blinks, then push the button.
4.9.193 Push the or button until <b>CORRECTION</b> menu title blinks, then push the
button.
4.9.194 Select current boom <b>LENGTH</b> by pushing the $\checkmark$ or $\checkmark$ and push the button.
4.9.195 Push the $\checkmark$ or $\checkmark$ button until <b>LOAD</b> menu title blinks, then push the $\checkmark$ button.
4.9.196 Push the $\checkmark$ or $\checkmark$ button until <b>P1</b> menu title blinks, then push the $\checkmark$ button.

4.9.197	Push the $\checkmark$ or $\checkmark$ button to change% until <b>ACT. LOAD = LOAD</b>
(Known	Weight + Block Weights + Deducts), then push the button.
4.10 E	Deflection (radius long boom) Calibration:
4.10.1	With boom fully extended at 60 degrees with no load on the hook.
4.10.2	Go to the <b>Calibration Menu</b> .
4.10.3	Push the $\checkmark$ or $\checkmark$ button until <b>SETUP</b> menu title blinks, then push the button.
4.10.4	Push the or button until <b>DEFLECTION</b> menu title blinks, then push the
	button.
4.10.5	Push the or button until OWN-WEIGHT menu title blinks, then push the button.
4.10.6	Measure actual radius with hook block only. Then change RADIUS indicated to actual radius, using the or buttons.
4.10.7	After RADIUS is set, push the button to exit.
	Push the $\checkmark$ or $\checkmark$ button until <b>LOAD</b> menu title blinks, then push the $\checkmark$ button.
4.10.9	Pick LOAD measure actual radius with hook block + test weight. Then change indicated
	RADIUS to actual RADIUS using the or buttons.
4.10.10	After <b>RADIUS</b> is set, push the button to exit.
	Push the $\checkmark$ button to EXIT then the $\checkmark$ button to the <u>Operating Screen</u> and enter the working display.

4.10.12 After Radius and Load Indication has been calibrated for this length it is recommended that a load moment shutoff be tested. Refer to next section .

#### 4.11 Load Moment Shut Off

- 4.11.1 To perform a load moment shut off for this configuration and length you are at.
- 4.11.2 You need Known weight + hook blocks + deducts = Test Weight.
- 4.11.3 After getting test load determine where the load should shut off is at either by radius or angle from the information on the load chart.
- 4.11.4 Start with the load at a higher angle than shut off and verify load indication is correct.
- 4.11.5 Slowly boom to the point of shut off. (If load indication is not correct as you are booming down return to section 4.9 and readjust the Ratio).
- 4.11.6 If system warning and shut off has functioned before calculated shut off point record the information from shut off on *LOAD MOMENT FIELD TEST SHEET* for this configuration provided with technical information booklet. This configuration is complete.
- 4.11.7 Go to the next configuration and start with section 4.9 4.11. Repeat this process until all configurations have been calibrated.


#### 4.12 MEASURE to generate Pressure Profiles

4.12.1 Fully retract and put the boom at 0 degrees 4.12.2 Go to the Calibration Menu. ER P Þ\$ 4.12.3 Push the button until MEASURE menu title blinks, then push the or button.  $\widehat{\mathbb{T}}$ 4.12.4 Push the button until AUTOMATIC menu title blinks, then push the  $\not\approx$ button. P ☜ until **CLEAR** menu title blinks, then push the 4.12.5 Push the button.  $\sim$  $\overline{\mathbb{T}}$ ¢⁄ợ 4.12.6 Select current boom **LENGTH** by pushing the or button and push the button. P ÞÞ 4.12.7 Push the button until EXIT menu title blinks, then push the button. P>  $\widehat{\mathbb{T}}$  $\dot{\mathbf{v}}$ button until MEASURE menu title blinks, then push the 4.12.8 Push the or button.

 $\Rightarrow$ button until OWN-WEIGHT menu title blinks, then push the 4.12.9 Push the P ÞÞ button.  $\overline{\diamondsuit}$ ₿ Ø 4.12.10 Select current boom **LENGTH** by pushing the button and push the button. P ¢¢ button until all digits have been verified to the proper value of the hook 4.12.11 Push the block + deducts weight. 4.12.12 Boom UP steady and slow, to highest boom angle before topping out the cylinder. P) Þ\$ **button.** If this procedure is not done Before you stop booming up, push the properly the CALCUTION of the pressure profile will not work. 4.12.13 Boom DOWN as close to 0 degrees as possible and select a known weight (load) for the known boom length (radius) that is within the load chart for the lowest boom angle. The larger the angle range with a weight over 1 ton the better the pressure profile. P> Ъ  $\odot$ 4.12.14 Push the button until LOAD menu title blinks, then push the or button. P  $\not\approx$ 4.12.15 Select current boom LENGTH by pushing and push the button. 5 P> ÞÞ 4.12.16 Push the button until all digits have been verified to the proper value, which will be the hook block + deducts + known weight. 4.12.17 Boom up steady and slow to 75 degrees or maximum angle on the load chart. Before P> ¢¢ completion of booming up, push the button.  $\odot$ ÞÞ 4.12.18 Push the button until **EXIT** menu title blinks, then push the button. or  $\overline{\mathbb{T}}$ button until **CALCULATION** menu title blinks, then push the 4.12.19 Push the or ÞÞ button. -¢∕⊄ Δ 4.12.20 Select current boom LENGTH by pushing the button and push the button. P> button to the Operating Screen and enter 4.12.21 Push the button to **EXIT** then the the working display.

#### CALIBRATION PROCEDURE

- 4.12.22 Verify pressure profiles are correct by checking the load indication at angle 0, 15, 30, 45, 60 and 70° with maximum boom length. If load indications are within 200 lbs., skip to <u>Step 4.9</u>. If indications are NOT correct, continue with the following procedure, which uses the MEASURE selection in the Calibration menu. Use the boom lengths specified in the Calibration Booklet to generate good profiles.
- 4.12.23 Fully extend and put the boom at lowest angle of the load chart for that boom length.
- 4.12.24 Go to the Calibration Menu.



P


P

- 4.12.37 Select current boom **LENGTH** by pushing the difference of the button and push the button.
- 4.12.38 Push the button until all digits have been verified to the proper value, which will be the hook block + deducts + known weight.
- 4.12.39 Boom up steady and slow, to 75 degrees or maximum angle on the load chart. Before

completion of booming up, push the  $\boxed{1000}$  button.

P>

- 4.12.40 Push the or button until **EXIT** menu title blinks, then push the button.
- 4.12.41 Push the or button until **CALCULATION** menu title blinks, then push the
- 4.12.42 Select current boom length by pushing the or button and push the button.
- 4.12.43 Push the button to **EXIT** then the button to the operating screen and enter the working display.
- 4.12.44 If all load indications are correct go to steps 4.10 and 4.11 to complete the calibration for this configuration. If load indication is not correct go to steps 4.9, 4.10 and 4.11 to complete the calibration for this configuration



### 6 CALIBRATION SUMMARY TABLE

This table is a summary of the calibration procedure and is not recommended for the first time user. Use this procedure as reference after reading, completing the calibration procedure and becoming familiar with console operation.

STEP	DESCRIPTION						
1.	Check that load chart booklet matches load chart in crane	Page 2					
WARNIN	IG: If the EPROMs are put into the sockets improperly they will be destroyed and new one be purchased.	es will have to					
2.	Install System, Data I, and Data II EPROMS						
3.	Enter Access Code: The ACCESS CODE Is <b>001001</b> .						
4.	CHECKSUM NEW EPROMS: CKSUM EP $\rightarrow$ CKSUM EEP $\rightarrow$ CKSUM PRG $\rightarrow$ RESET						
5.	Position Boom At $0^{\circ} \rightarrow$ Voltage sensor – mechanically adjust angle sensor to 1.0 VDC at terminal #1 and terminal # 5 (angle signal) in the cable reel.Page 3 & 4Current sensor – Use adjustment screws to align top of angle sensor parallel with boom at exactly 0°. (The measurement should read 20mA at 0°)Page 3 & 4						
6.	Fully Retract Boom $\rightarrow$ Voltage sensor – mechanically adjust length sensor to 1.0 VDC at terminal #1 and terminal #2 (length signal) in the cable reel. Current sensor – Adjust length potentiometer by turning center screw counter clockwise to a soft stop. The measurement should read between 4 20mA. ( $1V = 4mA$ and $5V = 20mA$ )Page 3 & 4						
7.	<ul> <li>Set Angle (refer to flow chart) → select:</li> <li>NORM, ANGLE, MINIMUM (match display with actual angle at 0°)</li> <li>Boom to max angle</li> <li>MAXIMUM (match display with the crane's actual maximum angle)</li> <li>ADJUST</li> <li>EXIT</li> </ul>	Page 4					
8.	Set Length (refer to flow chart) → select: NORM, LENGTH, MINIMUM-signal (match display with actual length), boom to max length, MAXIMUM-signal (match display with actual length), ADJUST, EXIT and fully retract boom.	Page 5					
9.	<ul> <li>Set Ratio → From the operating screen (refer to flow chart) →</li> <li>Select: SETUP,</li> <li>RATIO, while boom is stopped and load is steady,</li> <li>Record the ACT. LOAD from the display,</li> <li>Boom down slow</li> <li>Adjust the displayed ACT. LOAD to match the ACT. LOAD recorded, and exit.</li> </ul>	Pages 5 & 6					
Wa	rning: Operator is responsible for operating the crane within manufacturer's specified pa	rameters.					
10.	Select a known load that is within the load chart for the specified boom length or radius. For pressure profiles, the load should be greater than 1 ton and allow the boom to have the greatest range of angle movement. For testing, the load should be at least 75% of the rated load as read from the load chart.	Page 6					
11.	Check hook block and/or test load at: 0°, 15°, 30°, 45°, 60°, 75° are within 200lbs.PagesNote: Check the test load in crane configurations permitted by the load chart.Pages						
12.	If necessary, create pressure profiles using the boom lengths specified with calibration information. Use the same boom length throughout the following procedure and then repeating the procedure for each specified boom length. Refer to flow chart and select: • MEASURE, AUTOMATIC, CLEAR • Select boom length • EXIT	Pages 22-25					
	MEASURE, OWN-WEIGHT     Select boom length						

r				
	<ul> <li>Push PROGRAM button to begin calibration.</li> <li>Boom up steady and slow</li> <li>Before you get to the maximum angle and as the boom is moving up</li> <li>Push the PROGRAM button to create a pressure profile</li> <li>Pick the known load</li> <li>LOAD</li> <li>Select boom length</li> <li>Adjust the displayed load to match load (hook block + deducts + known weight)</li> <li>Push PROGRAM button to begin calibration.</li> <li>Boom up steady and slow</li> <li>Before you get to the maximum angle and as the boom is moving up</li> <li>Push the PROGRAM button to create a pressure profile</li> <li>EXIT</li> </ul>			
	EXII     CALCULATION			
	Select boom length			
	EXIT			
	Return to the operating screen.			
13.	<ul> <li>Correction of minimum boom length load. Refer to flow chart and select:</li> <li>SETUP, CORRECTION</li> <li>Select boom length</li> </ul>	Pages 7 & 8		
	<ul> <li>OWN WEIGHT, P1 – P4, ACT. LOAD indicates actual load = hook block + deducts</li> <li>EXIT</li> <li>LOAD, P1 – P4, ACT. LOAD indicates actual load = hook block + deducts + test weight.</li> <li>EXIT.</li> </ul>			
14.	Set radius offset $\rightarrow$ refer to flow chart and select: RADIUS OFFSET, measure actual radius Pages 7 and record, change radius to actual radius, and EXIT.			
15.	Check load and radius indications and check load moment shut off minimum boom.	Page 22		
16.	<ul> <li>Correction of middle (if required) and maximum boom length load. Refer to flow chart and select:</li> <li>SETUP, CORRECTION</li> <li>Select boom length</li> <li>OWN WEIGHT, P1 – P4, ACT. LOAD indicates actual load = hook block + deducts</li> </ul>	Page 14		
	<ul> <li>EXIT</li> <li>LOAD, P1 – P4, ACT. LOAD indicates actual load = hook block + deducts + test weight</li> <li>EXIT</li> </ul>			
17.	Set deflection $\rightarrow$ Refer to flow chart and select: DEFLECTION, OWN WEIGHT, measure actual radius with hook block only and record, change radius to actual radius, LOAD, , measure actual radius with load and record, change radius to actual radius, and EXIT	Page 21		
18.	Check load and radius indications and check load moment shut off. If load, angle, or length measurements are incorrect, repeat calibration procedure.	Page 22		

### HANDBOOK REVISIONS

REV	DATE	NAME	DESCRIPTION
-	01/12/00	CSH	Create calibration manual
Α	03/08/00	CSH	Added Menu Flow Chart and Calibration Summary Table
В	09/25/00	JF	Added more descriptions to existing calibration procedure,
			added corrections section and added button symbols.
С	03/02/08	SC	Add reference to calibration of current sensors
D	05/02/08	SC	Revise specs for calibration of current sensors
E	12/17/08	WG	Corrections to angle calibration

